# BRUHATH BENGALURU MAHANAGARA PALIKE

**Yelahanka Division, Yelahanka Zone**

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/19/2017-18 Dated: 17-02-2018

## APPROVED TENDER SCHEDULE –'B'

Item No: 25

Name of Work:Providing pot hole filling in ward no-01 of yelahanka Sub Division.

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri RAJANNA N | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1 ) | Cum | 505.12 | 174.66 | Rupees One Hundred Seventy Four and Paise Sixty Six Only |
| 2 | KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) | Cum | 505.12 | 104.95 | Rupees One Hundred Four and Paise Ninety Five Only |
| 3 | KSRRB M400- Wet Mix Macadam - KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 (P.No.157 & I.No.20.18) | Cum | 384.54 | 1855.60 | Rupees One Thousand Eight Hundred Fifty Five and Paise Sixty Only |

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri C RAJU | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 4 | filling of potholes and Patch Repairs with Bituminous Concrete ,40mm Removal of all failed material,trimming of completed exavation to provide firm vertical faces cleaning of surface, pai nting of tack coat on the sides and base of exavation as per clause 500.3,back filling the pot holes with hot bituminous material as per clause 500.4, compacting trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications MORTH specifications No.3004.2 (Page No.257/Item No.35.5) | Sqm | 2563.61 | 317.05 | Rupees Three Hundred Seventeen and Paise Five Only |
| 5 | KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3) | Sqm | 19.62 | 5414.39 | Rupees Five Thousand Four Hundred Fourteen and Paise Thirty Nine Only |
| 6 | KSRRB M600-6. Cement concrete pavement. Construction Un- reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 with 25mm and size graded granite metal , coarse and fine aggregate with superplastisiser @ 3lts conforming to IS9103-1999 Reaffirmed-2008, mixed in a concrete mixer of not less than 0.6cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved curing compound, finishing to lines and grades as per drawing complete as per specifications.(P.No.177 / It.No.22.6.1) | Cum | 20.03 | 5781.51 | Rupees Five Thousand Seven Hundred Eighty One and Paise Fifty One Only |

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64